

U.S. EMBASSY BELMOPAN

Solicitation No: 19BH2020Q0006

QUESTIONS & ANSWERS

Line	Questions	Answers
01	Will the concrete be sealed or not sealed?	Yes, concrete will be sealed.
02	Will concrete mixer trucks be allowed inside the compound?	Mixer trucks will be allowed inside the compound only if the location does not permit the concrete to be pumped from the outside.
03	When demolishing/removing the asphalt, will a Bobcat/small dump truck be allowed inside the compound?	Yes
04	Will there be a storage for materials?	Yes, we will provide a staging area for the materials.
05	Will a layout of the Jogging Trail be provided?	No, we are unable to locate a plan for the existing trail.
06	Will the contractor have to provide portable bathrooms for their workers?	Yes, the contractor will need to provide portable bathrooms and have them sanitized and cleaned daily.
07	Would it be permitted to place moisture barrier material before pouring Concrete in place of wetting the subgrade	Yes, but the subgrade still needs to be compacted.
08	Would small dump trucks be permitted inside the compound for removal of excavated materials	Yes.
09	Should the current asphalt be removed?	Remove asphalt and replace with 4ft wide concrete.
10	What should be underneath?	Subbase should be underneath.
11	What should be the level of the concrete?	Level of concrete should be at the level with the land/grass.
12	What layout should the concrete follow?	The concrete should follow the layout of the land
13	What finish should the concrete have?	The concrete must have a brush finish.